

STATINTL

Renovations

(The following is keyed to the attached blueprint.)

GENERAL ITEMS

Window Grilles on windows

Motorize main entrance overhead door

Remove miscellaneous lighting fixtures and conduit, branch circuits and outlets

Install new interior lighting system convenience power and special power

Install exterior lighting

Paint interior walls and ceiling

Seal and seal floors

General building and floor cleanup

General heating system

Compressed air system

Gas pumps and 10,000-gallon tank

Internal fire alarm system

Fire extinguishers

ROOM A (Entrance)

No modifications

ROOM B (Parking Area)

Fill in slab depression

ROOM C (Repair Shop)

Install louvers in three window fans

Fill in slab depressions

Extend and enlarge existing ramp

Install fire door in opening to paint shop

Fill opening between paint shop and repair shop

Install six position automobile trunk exhaust system

ROOM D (Clerical Office)

Construct vestibule

Repair air-conditioning unit

Repair and seal walls and ceiling

ROOM E (Private Office)

No modifications

ROOM F (Automotive Parts Storage)

Remove two masonry masses on floor

Cut opening and install door in north wall

Construct stair and landing

ROOM G (Body Shop)

Remove wood platform construction

Remove and cap existing sump pit

Install exhaust fan in lower window

Construct stair and landing

ROOM H (High Density Parking)

Remove existing partitioning

Construct ramp from alley door

Enlarge east wall door opening

Block opening into Room N (toilet)

ROOM I (Locker-Shower-Guard Complex)

Remove all temporary partitioning

Patch holes in ceiling

Construct partitioning around dayroom - locker room - guard

Modify existing toilet (1/1) and construct toilet shower complex

Install four window air-conditioning units

ROOM J (High Density Parking)

Replace plumbing for existing soapstone sink and drainboard

ROOM K (Battery-Tire Storage and Compressor Room)

No modifications

ROOM L (Truck Port)

Install four electricity-operated, overhead, rolling grilles between exterior columns

ROOM M (Lubrication Area)

Install hydraulic lift

Install overhead lubricating equipment

Fill in voids of south end wall (18' x 14')

Repair uneven floor

Provide floor drain

ROOMS Q & P (Toilets)

Remove fixtures, walls, ceilings, and cap plumbing

ROOMS Q, R, & N (Toilets)

Remove and replace all fixtures

Scrape, clean, paint, and repair all surfaces